Approved For Release 2001/04/09: CIA-RDP78-05327A000300040034-2

SECTION 26

METHOD OF MEASUREMENT AND BASIS OF PAYMENT

26-01 METHOD OF MEASUREMENT: No measurement for payment will be made for the work covered under Sections 1 through 18, including 5A and 16A, and all costs in connection therewith shall be included in the contract unit prices for the buildings or structures involved. Work covered under Sections 19 through 25 will be measured for payment, in place, by the units of measurement indicated in the schedule of unit prices.

26-02 BASIS OF PAYMENT: Payment will be made for the actual quantities measured in place in accordance with the provisions of the preceding paragraph, at the applicable contract unit price for each item of work indicated in the schedule of unit prices, which payment shall constitute full compensation for furnishing all supervision, plant, labor, materials, equipment, supplies, transportation, including fuel, power and water (except any materials, equipment, utilities or services, if any, specified herein to be furnished by the Government) and for performing all operations required to complete each item of work in accordance with the specifications, schedules and drawings, and subject to the terms and conditions of the contract.

Approved For Release 2001/04/09: CIA-RDP78-05327A000300040034-2

STATE OF THE PARTY OF THE PARTY

SECTION 27

DISMANTLING, DEMOLITION, SALVAGE, AND DISPOSITION OF BUILDINGS

27-Ol SCOPE: The work covered by this section of the specifications consists in furnishing all plant, labor, equipment, appliances, and materials not furnished by the Government, and in perferning all operations in connection with the dismentling, denolition, salveging, and disposition of existing buildings, complete in strict accordance with this section of the specifications and the applicable drawings, and subject to the terms and conditions of the centract.

27-02 WORK TO BE PERFORMED:

- a. General: Quonset buildings indicated on the drawings or by the Centracting Officer shall be dismantled and/or demolished and removed from the site. The Centractor shall become the sole owner of the dismantled or demolished buildings, including all equipment and materials salvaged from them.
- b. <u>Disconnection of Services:</u> Before starting work on the buildings, the utilities, connections, or services thereto shall be disconnected, and the mains scaled in a manner approved by the Contracting Officer.
- (1) All poles, accessories and other naterials of the electric supply lines to the buildings shall be removed in a nanner to prevent demage, shall remain the property of the Government and shall be transported to storage points indicated by the Contracting Officer.

c. Dismontling and Demolition:

- (1) Schedule of Work: Work shall be started and conpleted in order of precedence as established by a schedule of work approved by the Centracting Officer, and prepared before any work is begun.
- (2) <u>Buildings:</u> Buildings shall be dismontled and/or demelished as hereinafter prescribed. Previsions, approved by the Centracting Officer, shall be made to avoid interference with the use of adjoining buildings or the interruption of free passage thereto. Operational precedures and sequences for dismontling and demolition work shall be optional with the Centractor insefer as they do not infringe on the work schedule approved by the Centracting Officer. The sequence of operations shall be such as to provide safe working a conditions. All concrete feeting, foundations and slabs, if any, shall be demolished and removed to the extent and in a manner as will not interfere with construction and as approved by the Centracting Officer.

Approved For Release 2001/04/09 : CIA-RDP78-05327A000300040034-2

- (3) <u>Dynamite and Paydori</u> No dynamite or powder shall be used for blasting nor brought to the site except on prior written permission of the Contracting Officer.
- (4) Protection of Persons and Property: Adequate protection of persons and property shall be provided at all times. The work shall proceed in such namer as to prevent the undue spread of dust and flying particles.
- (5) Burning of noterials and bebris: No materials or debris shall be burned on the premises except under such previsions and in such manner as specifically approved by the Contracting Officer.

27-03 PAYMENT: We payment will be made by the Centractor to the Government for the quenset buildings which become the property of the Centractor and the volues of which will be considered as partial componentian to the Centractor for the work under this contract, in addition to those stipulated on the Unit Price Schedule. No separate payment will be made to the Centractor for the discentling and removal of the quenset buildings, which work will be considered as subsidiary obligation of the Centractor under this centract.

27-04 CLEANING UF: Upon completion of dismontling, all salvaged material shall be removed as soon as precticable and in a manner approved by the Centracting Officer. When material designated for scrap is burned, proper precautions and previsions shall be affected for the protection of property from effects of the fire. The burned-ever area shall be raked clean and any unburned debris shall be disposed of as fill or as otherwise directed by the Centracting Officer.